

## UCCS Breckenridge House AV Refresh-Addendum #1

Owner:

University of Colorado – Colorado Springs

Consultant:

Eleven Tech Group

Project:

Breckenridge AV Refresh- Project #17-012

Addendum #1 – Additional Clarification & Exclusions:

- A. Remove all instances of Mersive Solstice Pod BYOD collaboration device from all rooms in the project scope. This feature will be implemented at a later date.
- B. Remove all Epson projectors & lenses from the equipment list. Epson projectors are now classified as Owner Furnished, Contractor Installed. The owner has elected to procure the projectors directly from Volcom and will be responsible for receiving the equipment and delivering to the awarded AV integrator. Please exclude the projectors from your warranty statement but include the installation, configuration, alignment & commissioning of the projectors in your project scope of work.
- C. Include in your scope of work assumptions “backing for wall mounted devices to be provided by AV contractor as required. Owner to provide painting/finishing of contractor supplied backing with 48 to 72 hour notice.”
- D. Exclude from your project scope decommissioning, removal and storage of the existing AV equipment in Room 5101. This work will be performed by the owner’s electrical contractor.
- E. Exclude from your project scope network cabling to relocate the Crestron CEN-GWEXER wireless gateway to the first floor electrical closet. This will be moved to the data cabling contractor’s scope. Include mounting, configuration & commissioning of the gateway in your project scope of work.
- F. Exclude the installation of the Crestron CLW-DIMEX-E & CLW-SWEX-E lighting dimmers & switches. These are to be purchased by the AV Contractor and installed by the owner’s electrical contractor. Include configuration & commissioning of the devices.
- G. Include in the equipment list a quantity of four (4) Crestron HD-DA-2 to be used for audio de-embedding to provide a dedicated audio feed to the owner provided Assisted Listening System. Include in your project scope assumptions “Further coordination shall be provided to the awarded AV contractor by the AV consultant to verify required functionality of interface to owner provided ALS system”.
- H. Include in your scope of work assumptions receipt of the PDF “Extron MLM\_WB\_Plus\_ADA\_Compliance\_68-1456-01\_B” regarding the installation of the Extron wall racks in Rooms 5104, 5106 and 5113.
- I. Include in your scope of work assumptions receipt of Cucharas Site Survey pictures. Please review these pictures for coordination of the Extron wall rack, Crestron touch panel, Dell AiO PC’s and wall mount in Rooms 5104, 5106 and 5113. Note these pictures show a recessed installation of the MLM-WB+ wall rack which will not be required for this project.
- J. Include in your scope of work assumptions receipt of PDF “UCCS-Breckenridge AV Project 17-012\_Plates 5.17.2017” regarding wall plate details.
- K. Include in your scope of work assumptions receipt of this Addendum #1 dated 6.9.2017.

Requests for Information & Bid Due Date

- A. RFI’s to be submitted to Jeff Davis no later than 12PM June 12, 2017.
- B. RFI replies to be posted by close of business on June 12<sup>th</sup>.
- C. All bids due Wednesday June 14<sup>th</sup>, 2017.